

ヨドバシ仙台第一ビル計画に係る事業計画の変更
及び環境影響の再予測評価について

【報 告】

令和3年3月

株式会社ヨドバシホールディングス

表1-13(2) 主要重機の稼働台数 (変更後)

| 項目 | 令和3年 | | | | | | | | | | | | 令和4年 | | | | | | | | | | | | 令和5年 | | |
|----------------------|---------|-----|-----|-----|-----|-----|-----|-------|-------|-------|-----|-------|-------|-------|-----|-----|-----|-----|-----|-----|-----|-----|----|----|------|---|---|
| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 1 | 2 | 3 |
| 検査 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 工事工程 | 準備工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 山留工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 切梁・棧橋工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 掘削工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 躯体工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 鉄骨工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 仕上工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 外構工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 試験・山留工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 掘削・埋戻工事 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 躯体工事 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 発電機(125KVA) | 25 | 50 | 75 | 125 | 67 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| バックホウ(0.7m³) | 12 | 25 | 25 | 14 | 53 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| バックホウ(0.4m³) | 0 | 0 | 0 | 139 | 134 | 110 | 120 | 168 | 72 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| クラムシエル(1.0m³) | 0 | 0 | 0 | 0 | 0 | 96 | 120 | 168 | 72 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| ラフタークレーン(50t) | 0 | 0 | 0 | 0 | 0 | 34 | 62 | 60 | 60 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 0 | 0 | 0 | | |
| ラフタークレーン(25t) | 12 | 25 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 36 | 0 | 0 | 0 | | |
| クローラクレーン(70t) | 0 | 0 | 0 | 125 | 67 | 0 | 0 | 48 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 0 | 0 | 0 | | |
| クローラクレーン(120t) | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| タワークレーン(600t) | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| コンクリートポンプ(60~70m³/H) | 0 | 0 | 10 | 10 | 0 | 0 | 5 | 25 | 38 | 12 | 10 | 25 | 27 | 28 | 21 | 23 | 16 | 16 | 16 | 16 | 16 | 16 | 0 | 0 | 0 | | |
| コンクリートミキサー(4.3m³) | 0 | 0 | 20 | 100 | 200 | 200 | 250 | 730 | 950 | 870 | 500 | 800 | 1,000 | 750 | 730 | 700 | 680 | 650 | 650 | 650 | 650 | 650 | 0 | 0 | 0 | | |
| 工事用エレベーター(2.0tクラス) | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| フィニッシャー(6.0mクラス) | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| 重機月稼働総台数 | 49 | 100 | 155 | 503 | 555 | 523 | 580 | 1,224 | 1,326 | 1,076 | 704 | 1,019 | 1,257 | 1,008 | 981 | 953 | 779 | 727 | 727 | 727 | 727 | 81 | 81 | 81 | | | |

